

# **DABHI ENGINEERING ASSOCIATES INC.**

19310 Kessington Lane; Houston, Texas 77094  
TEL (281) 492-6885; FAX (281) 492-8626

AT&T–Galveston W. Island C.O  
Installation of new Air Conditioning Units

## **ADDENDUM #1 (05/13/2018)**

Addendum #1 consists of the following comments/revisions to the bid drawings. Addendum #1 in its entirety shall be incorporated into contractors' bids:

1. M1.01: New Air Cooled Condensing Unit Schedule:
  - A. (N) ACCU-2, Note-4 shall be deleted. Rawl capacity control valve with all accessories is not required.
2. DWG. M1.03, the existing single door in the loading room existing in the telephone switch room: Furnish and install 4" wide X4" high concrete curb just outside the door in telephone switch room to prevent a probable water leakage into the room. It shall be reinforced with #3 rebars, bonded to the floor with epoxy, and water-proofed.
3. DWG. E1.02:
  - A. Furnish and install new ¾" EMT cond from new FA devices to the existing FACP. Furnish and install new ¾" EMT cond from new FA devices to the existing FACP.
  - B. Furnish and install new ¾" EMT cond from new FA devices to the existing PNL-L with (3), #12 (ph, neut, gnd) wires. Use (1), spare 20 amp, 1 pole CB of pnl board to serve this load.
  - C. Furnish and install new ¾" EMT cond from new BAS devices in the loading room to the existing PNL-L with (3), #12 (ph, neut, gnd) wires. Use (1), spare 20 amp, 1 pole CB of pnl board to serve this load.

END