

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF ALTERNATES

A. Alternate No. 1

1. Base Bid: Install the millwork at North elevation of Multi-Purpose room 1010 and install 2nd millwork serving line. Re: A2.01 for millwork locations. Re: E200 for relocation of existing duplex outlets at North elevation millwork.
2. Alternate: Delete millwork at North elevation of Multi-Purpose room 1010 and delete 2nd millwork serving line as indicated on the drawings. Re: A2.01 for locations of millwork to be deleted. Existing electrical outlets associated with North elevation millwork would remain as existing.

B. Alternate No. 2

1. Base Bid: Install (3) millwork units as indicated on Sheet A2.01. These units include the entry screen millwork, the screen wall in front of the Auditorium and the front serving line millwork.
2. Alternate: Delete a total of (3) millwork units: the entry screen millwork, the screen wall in front of the Auditorium and the front serving line millwork as indicated on the drawings. Deletion includes all electrical directly associated with these units including duplex outlets and lighting fixtures.

C. Alternate No. 3

3. Base Bid: Install the (2) freestanding millwork units in Lounge 1010A as indicated on Sheet A2.01.
4. Alternate: Delete the (2) freestanding millwork units in Lounge 1010A as indicated on Sheet A2.01. Deletion includes all electrical directly associated with these units including duplex and data outlets.

D. Alternate No. 4

5. Base Bid: Provide and install pendant fixture types B, C and D including lighting controls.
6. Alternate: Delete pendant fixture types B, C and D. Deletion includes all lighting controls, conduit and patching / repair of existing ceilings directly associated with the installation of these fixtures.

E. Alternate No. 5

7. Base Bid: All work associated with the installation of new hand wash sink in Prep Area 1019. Base bid includes the trenching of the existing concrete slab to install under-floor piping for new scheduled sink and repairs of existing room finishes in impacted areas. Re: A1.02
8. Alternate: Install scheduled hand wash sink and scheduled sump pump in the Prep Area 1019 as indicated on Plumbing Sheet P100. Alternate includes patch/repair of adjacent build out to accommodate above ceiling installation of plumbing lines. Re: A1.02 and A1.03 for architectural scope of work.

END OF SECTION 01 23 00