

May 24, 2018 - 3:44pm
 S:\projects\17323 - HCA Cy Fair Medical Center Hospital - Neuro and Shock ICU Finishes\CAD\Sheets\A2_01 Floor Plan.dwg
 william.panganiban



GENERAL NOTES

- A. CONTRACTOR SHALL COORDINATE AND VERIFY EXACT LOCATION OF ALL EXISTING PIPES PRIOR TO CONNECTION AND REMOVAL.
- B. PROJECT DOES NOT ADD OR REVISE ANY EXISTING FIRE RATED PARTITIONS AND SYSTEMS.
- C. PROVIDE TEMPORARY FIRE EXTINGUISHERS IN ACCORDANCE WITH NFPA 10 AT WORK AREA.
- D. PATCH AND REPAIR ALL EXISTING WALLS AND FLOORING TO REMAIN, PREP TO RECEIVE NEW PAINT AND SCHEDULED FINISHES.
- E. CONTRACTOR SHALL COORDINATE SCHEDULE WITH OWNER.
- F. PROVIDE FIRE RETARDANT TREATED WOOD NONCOMBUSTIBLE BLOCKING BEHIND EQUIPMENT, ACCESSORIES, FURNITURE, ETC. COORDINATE LOCATIONS.
- G. FINISH FACE OF NEW PARTITIONS SHOWN AS CONTINUING FROM AN EXISTING PARTITION SHALL ALIGN SEAMLESSLY AND FLUSH. NOTICEABLE JOINTS WILL NOT BE ACCEPTABLE.
- H. VERIFY LIGHT SWITCH LOCATIONS WITH OWNER.
- I. NURSE CALL DEVICES TO REMAIN
- J. INSTALL MATERIALS STRICTLY BY MANUFACTURER'S INSTRUCTIONS, INCLUDING RECOMMENDED AND COMPATIBLE SUBSTRATES (AND ADHESIVES).
- K. OFFSET HINGES COORDINATE WITH DOOR FRAMES
- L. ELECTRICAL DEVICE COVER PLATES ARE TO BE BUILDING STANDARD.

NOTES TO SHEET

- 1 EXISTING FIRE EXTINGUISHER CABINET
- 2 EXISTING HEADWALL PANEL SYSTEMS TO REMAIN. PROVIDE NEW P-LAM ON EXISTING PANEL INSERTS, ADD NEW FLAT PANEL INSERT (AT VACUUM COVE); CONTACT: DYANA CARDENAS 925-427-7800
- 3 NEW P-LAM DOOR WITH INTEGRAL BLINDS VISTAMATIC; RE: A9.01 AND INTERIORS
- 4 PROVIDE FAUX-WOOD BLINDS; RE: INTERIORS
- 5 NEW GRAB BARS TO REPLACE EXISTING GRAB BARS
- 6 PROVIDE NEW WALL PROTECTION/CRASH RAILS; RE: INTERIORS
- 7 PROVIDE WALL BLOCKING FOR NEW FLAT SCREEN TV
- 8 (14) NEW DOUBLE STACKED METAL LOCKERS; RE: SPECS
- 9 EXISTING MILLWORK; RE-LAMINATE WITH SCHEDULED P-LAM
- 10 NEW WARDROBE AND SHELF MILLWORK; RE: INTERIORS FOR FINISHES
- 11 FOR EXHAUST STACK AND DETAILS; RE: M2.02 AND M3.01

LEGEND TO SHEET

- NEW PARTITIONS
- EXISTING WALL TO REMAIN
- NOTE TO SHEET
- DOOR KEY; RE: A9.01
- INTERIOR ELEVATION KEY (RE:A7.01)
- TOILET ACCESSORY DESIGNATION; RE: TOILET ACCESSORY LEGEND
- EQUIPMENT DESIGNATION
- EXISTING MEDICAL GASES
- EXISTING CONSTRUCTION OUTSIDE SCOPE OF WORK

TOILET ACCESSORY LEGEND

TAG	DESCRIPTION	MANUFACTURER	CFCI	OF CI
B1	PAPER TOWEL DISPENSER	GEORGIA PACIFIC AUTOMATED, SURFACE MOUNTED, HARDWOOD, MODEL NO. 58470	X	
B2	SURFACE MOUNTED PAPER TOWEL DISPENSER	BOBRICK B262		X
D1	TOILET PAPER DISPENSER	BOBRICK B-6857	X	
E1	SOAP DISPENSER	BOBRICK B2-1111		X
G1	GRAB BAR	BOBRICK 6806 WITH SATIN FINISH	X	
L1	DOUBLE ROBE HOOK	BOBRICK B-6727 MOUNTED WHERE INDICATED AT 48" AND 72" A.F.F.	X	
L2	DOUBLE WALL HOOK	ALNO ALN-55765, MOUNTED BEHIND DOOR ON WALL AT 34" AND 72" A.F.F.	X	
M1	MIRROR	BOBRICK B-290 2436	X	
M2	LIGHTED MIRROR	LUMIDESIGN, AMBER, 22" X 40", LED, 3000K	X	

OWNER FURNISHED OWNER INSTALLED EQUIPMENT

- 1 COMPUTER STATION, RE: ELEVATION
- 2 PATIENT BED, RE: ELEVATION
- 3 PATIENT TV, RE: ELEVATION
- 4 PRINTERS/FAX, RE: ELEVATION
- 5 UNDER COUNTER REFRIGERATOR
- 6 MICROWAVE
- 7 REFRIGERATOR
- 8 MULTI-COPIER
- 9 COFFEE MAKER
- 10 PYXIS
- 11 CRASH CART
- 12 SHARPS CONTAINER, 4 GAL.
- 13 BATTERY OPERATED CLOCK
- 14 WATER COOLER

OWNER FURNISHED CONTRACTOR INSTALLED EQUIPMENT

- 50 ICE AND WATER DISPENSER
- 51 TV BRACKET
- 52 NOT USED
- 53 PATIENT STATUS SMART BOARD

HEITKAMP SWIFT ARCHITECTS
 Architecture • Interiors • Planning
 1165 BRITTMOORE ROAD HOUSTON TEXAS 77043
 (T) 713.628.4300 (F) 713.628.4301

in association with:
Garner-Fritzsche ENGINEERING, INC.
 8554 Katy Freeway, Suite 101 Houston, TX 77024
 713.432.1422 - Fax 713.432.1253
 www.garnerfritzsche.com

{b} bennett design group
 1165 Brittmooore Road Houston, Texas 77043
 p: 713.850.8833 f: 713.850.0383

Cypress Fairbanks Medical Center Hospital
 An HCA Affiliated Hospital
 10655 Steepletop Drive Houston, TX 77065

NEURO/SHOCK ICU FINISH UPGRADE



REVISIONS

NO.	ISSUE	DATE
1	Addendum 1	05-22-18

Sheet Information

DATE	05/14/2018
JOB NUMBER	17323
TITLE	FLOOR PLAN

SHEET
A2.01

FLOOR PLAN

1/4" : 1'-0"

1